

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-19066-00-02
Spot: SESWSW Sec/Twnshp/Rge: 10-19S-10W
333 feet from S Section Line, 3970 feet from E Section Line
Lease Name: ARENS-WILKEN Well #: 1-2
County: RICE Total Vertical Depth: 3520 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	3387		0 SX
SURF	8.625	183		140 SX

Well Type: SWD UIC Docket No: D18385.0 Date/Time to Plug: 08/19/2016 12:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: GAYLARD UNRUH Company: Phone: (785) 483-1426

Proposed Plugging Method: PLUG WELL WITH TUBING DOWN HOLE WITH CEMENT & NO CASING RETRIEVAL.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 08/23/2016 9:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, pull 20 jts.tubing and packer. Run in with impression block and found tubing fish at approx. 1800'. Got some tubing out to 1860' where heavy iron sulfide, etc. was encountered, decided to plug well. Run tubing to 1837' and pumped 35 sx's common with 4% CC. Pull tubing up 400' and wait 1 hr. Lower tubing back down to 1837', - DID NOT tag cement. Pumped 35 more sx's with 4%CC and 100 #'s cotton hulls. Wait another hour and tagged cement at 1686'. Pull tubing to 1250' and pump 35 sx's common cement with 3% CC. Pull tubing up to 900' and wait 1 hr. Lower tubing back down and DID NOT tag cement. Pumped 75 sx's common cement at 1250' and let set overnight. Came back on 8/23/16 and tagged cement at 990'. Pulled tubing to 900' and pumped 35 sx's cement, pulled tubing to 250' and pumped 110 sx's cement to surface-circulated out of both casings. Pulled tubing out and topped off with 10 sx's.

Top	Bot	Thru	Comments
3387	3520	OH	

Remarks: WELL WOULDN'T PASS PRE-MIT. GEMINI PERF TICKET #2371. QUALITY CEMENT TICKET #7821 ON 8/22/16. & #7814 ON 8/23/16.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

OCT 04 2016

Form CP-2/3

Heidi Olenick
CC UIC

1/3K