

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-059-23207-00-01
Spot: SESESESW Sec/Twnshp/Rge: 28-15S-20E
146 feet from S Section Line, 2951 feet from E Section Line
Lease Name: HARRY SCOTT Well #: 1A
County: FRANKLIN Total Vertical Depth: 800 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	776		83 SX
SURF	6.25	42		15 SX

Well Type: EOR UIC Docket No: E24111.47 Date/Time to Plug: 08/05/2016 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: REX R. ASHLOCK OR RICK Company: Phone: (620) 365-3111

Proposed Plugging Method: IF CANNOT "CEMENT SQUEEZE" DOWN THE PROD CSG, WILL RIH 1" TBG TO BTM AND FILL SAME W/ CMT, POOH TBG, "TOP OFF" PROD CSG W/ CMT, PRESS UP ON PROD CSG, AND SIW. RETURN AT A LATER DATE, DIG DOWN BELOW "PLOW LEVEL" CUT OFF SURF AND PROD CSG, THEN BACK FILL HOLE W/ SOIL.

Plugging Proposal Received By: LEVI SHORT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/05/2016 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO 800 FEET IN 2-1/2 INCH AND FILL TO SURFACE WITH CEMENT.
PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 300 PSI. USE TOTAL OF 25 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
721	730		
RECEIVED KCC DIST # 3 SEP 28 2016 CHANUTE, KS LS			

Remarks: FAILED MIT.

Plugged through: TBG

OCT 04 2016
Nedra Dennis
CC UIC

District: 03

Signed *L. Short*

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 03 2016
CONSERVATION DIVISION
WICHITA, KS