

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-059-23219-00-01  
Spot: SWSWSWSE Sec/Twnshp/Rge: 28-15S-20E  
153 feet from S Section Line, 2352 feet from E Section Line  
Lease Name: HARRY SCOTT Well #: 3A  
County: FRANKLIN Total Vertical Depth: 800 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	783		78 SX
SURF	6.25	42		15 SX

Well Type: EOR UIC Docket No: E24111.48 Date/Time to Plug: 08/24/2016 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: REX R. ASHLOCK OR RICK Company: Phone: (620) 365-3111

Proposed Plugging Method: IF CANNOT "CEMENT SQUEEZE" DWN THE PROD CSG, WILL RIH 1" TBG TO BTM, PMP CMT THRU SAME FILLING THE PROD CSG, THEN POOH TBG, "TOP OFF" PROD CSG W/ CMT, PRESS UP ON CSG, AND SWI. RETURN AT A LATER DATE, CUT ALL CSG OFF BELOW "PLOW DEPTH", BACK FILL HOLE W/ SOIL, AND CLEAN UP THE LOC.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE  
Date/Time Plugging Completed: 08/24/2016 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO 780 FEET IN 2-1/2 INCH AND FILL TO SURFACE WITH CEMENT. PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 150 PSI. USE TOTAL OF 25 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
737	745		
RECEIVED KCC DIST # 3 SEP 28 2016 CHANUTE, KS  LS			

Remarks: FAILED MIT.

Plugged through: TBG

OCT 04 2016  
*Nedra Plenic*  
CC UIC

District: 03

Signed *L Short*

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 03 2016  
CONSERVATION DIVISION  
WICHITA, KS