

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-27848-00-00
Spot: SESWNE Sec/Twnshp/Rge: 26-30S-16E
2165 feet from N Section Line, 1815 feet from E Section Line
Lease Name: DICKENS Well #: 101
County: WILSON Total Vertical Depth: 1067 feet

Operator License No.: 31941
Op Name: 3 B ENERGY, INC.
Address: PO BOX 354
NEODESHA, KS 66757

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1053		143 SX
SURF	6.25	21		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2016 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: SHARON WOHLER Company: 3 B ENERGY, INC Phone: (620) 779-0153

Proposed Plugging Method: HOOK ON TO 4-1/2" AND PUMP FULL OF CEMENT BY USING THE SQUEEZE METHOD. SHUT IN WITH PRESSURE.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 08/16/2016 8:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The 4.5 inch wellhead was hooked onto directly. 12 bbls of water was pumped to establish flow. The well was then pumped full of cement that contained cottonseed hulls. The well was pumped full by squeezing. The well was then shut in with 500 psi. A total of 98 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
1032	1036		
922	928		

RECEIVED
KCC DIST # 3
SEP 29 2016
CHANUTE, KS
AD

Remarks:

Plugged through: CSG

District: 03

Signed _____

(TECHNICIAN)

OCT 04 2016

Form CP-2/3

Received
KANSAS CORPORATION COMMISSION

OCT 03 2016

CONSERVATION DIVISION
WICHITA, KS