

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24879-00-00  
Spot: SESENW Sec/Twnshp/Rge: 16-16S-13W  
3250 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: WITTIG SHELTON Well #: 2  
County: BARTON Total Vertical Depth: 3385 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3382		150 SX
SURF	8.625	474		325 SX
TI	2.875	3378		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/11/2016 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (785) 483-2169

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/11/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations to 3000' and topped with 5 sx cement. Cut casing at 2220'. Pulled casing to 1460' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 400'. Circulated cement to surface with 100 sx cement. Pulled casing and topped off with 15 sx cement.

GPS: 38.66120 -098.76669

Perfs:

Top	Bot	Thru	Comments
3273	3279		
3216	3220		
3152	3158		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

SEP 06 2016

CONSERVATION DIVISION  
WICHITA, KS

OCT 04 2016  
*No*

Form CP-2/3

AUG 15 2016