

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25186-00-00
Spot: SWNNWSW Sec/Twnshp/Rge: 4-16S-14W
2050 feet from S Section Line, 260 feet from W Section Line
Lease Name: KARST-NUSS UNIT Well #: 1
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3441		140 SX
SURF	8.625	442		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2016 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL CORP. Phone: (785) 483-2169

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations to 3000' and topped with 5 sx cement. Cut casing at 2270'. Pulled casing to 1468' and pumped 125 sx cement w/200 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 400'. Circulated cement to surface with 125 sx cement. Pulled casing and hole stayed full.

GPS: 38.66120 -098.76669

Perfs:

Top	Bot	Thru	Comments
3394	3400		
3384	3388		

Remarks: GLOBAL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

SEP 06 2016

CONSERVATION DIVISION
WICHITA, KS

AUG 17 2016

OCT 04 2016
no

Form CP-2/3