

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24387-00-00
Spot: NWNENE Sec/Twnshp/Rge: 8-16S-21W
5199 feet from S Section Line, 1059 feet from E Section Line
Lease Name: LAMER ZELLER Well #: 1
County: NESS Total Vertical Depth: 4359 feet

Operator License No.: <u>8996</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>MID-CONTINENT RESOURCES, INC.</u>	PC		1688		WITH 165 SX CMT
Address: <u>PO BOX 399</u>	PROD	5.5	4354		WITH 150 SX CMT
<u>GARDEN CITY, KS 67846</u>	SURF	8.625	234		WITH 160 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/14/2016 10:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: MID-CONTIENT RESOURCES Phone: (620) 275-2963

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 100 SX CMT & 400# HULLS. PULL TBG TO 1700' & CIRCULATE CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2016 2:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

Actual Plugging Report	Top	Bot	Thru	Comments
CASING COLLAPSED AT 2650'. CANNOT GET PAST THAT DEPTH. RUN TBG TO 2600' & SPOT 100 SX CMT & 200# HULLS. PULL TBG TO 1700' & PUMPED 190 SX CMT & 200# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500#. TOPPED OFF WITH 30 SX CMT.	4239	4246		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
SA (TECHNICIAN)

RECEIVED
SEP 20 2016
KCC DODGE CITY

OCT 04 2016
no Form CP-2/3