

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21784-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 27-19S-28W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: STORMONT A Well #: 1-27
County: LANE Total Vertical Depth: 4710 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4290		WITH 2 SX CMT
DVT		2146		WITH 450 SX CMT
PROD 5.5		4705	0	WITH 175 SX CMT
SURF 8.625		206		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2016 8:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: DAVID OLLER Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: CIBP @ 4300' WITH 2 SX CMT. FILL VOID BACK TO 2300'. FILL 5 1/2" WITH CMT FROM 2300' TO SURFACE. PUMP CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 08/18/2016 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4290' WITH 2 SX CMT. PUMPED 240 SX CMT DOWN CASING TO 2200'. PRESSURED TO 500#. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4347	4357		
2145	2146		

Remarks: USED 60/40 POZMIX HURRICANE SERVICES.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
5A

(TECHNICIAN)

RECEIVED
AUG 30 2016
KCC DODGE CITY

OCT 04 2016
no

Form CP-2/3