

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-21587-00-00
Spot: NWNW Sec/Twnshp/Rge: 13-35S-35W
660 feet from N Section Line, 660 feet from W Section Line
Lease Name: FARLEY Well #: 1-13
County: STEVENS Total Vertical Depth: 6851 feet

Operator License No.: 5263
Op Name: MIDWESTERN EXPLORATION COMPA
Address: 3500 S BOULEVARD STE 2B
EDMOND, OK 73013

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5895		WITH 2 SX CMT
CIBP		6250		WITH 2 SX CMT
CIBP		6540		
PROD	4.5	6716	1645	WITH 250 SX CMT
SURF	8.625	1630		WITH 650 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/07/2016 8:00 AM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: MARTY Company: MIDWESTERN WELL SERVICE, IN Phone: (620) 624-8203

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 09/07/2016 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 6250' WITH 2 SX CMT. SET CIBP @ 5895' WITH 2 SX CMT. 1ST PLUG AT 1660' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6578	6592		
6422	6430		
6300	6320		
5945	5952		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
SEP 12 2016
KCC DODGE CITY

OCT 04 2016

Form CP-2/3