

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-20788-00-00
Spot: E2W2NESW Sec/Twnshp/Rge: 10-16S-26W
2040 feet from S Section Line, 3319 feet from E Section Line
Lease Name: PETERS D Well #: 1
County: NESS Total Vertical Depth: 4561 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4500		WITH 2 SX CMT
PROD	5.5	4570	0	WITH 100 SX CMT
SURF	8.625	327		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2016 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OFS, LLC
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN L LOEB Phone: (618) 943-2227

Proposed Plugging Method: CIBP @ 4500' WITH 2 SX CMT. LOAD HOLE & TEST. PERFORATE AT 2100' WITH 50 SX CMT & 100# HULLS IN LAST 25 SX CMT. PERFORATE AT 1250' WITH 80 SX CMT OVER CASING VOLUME, 150 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2016 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CIBP @ 4500' WITH 2 SX CMT. LOAD & TEST CASING TO 700#. HOLDING. RUN CBL. TOC ON BOTTOM AT 4500'. ALSO HAVE CMT FROM 2490' TO 1740'. PERFORATE 2 HOLES AT 1230'. INJECTION RATE 2 BPM @ 1100 PSI DOWN CASING. NO BLOW OR CIRCULATION UP THE 5 1/2" X 8 5/8" ANNULUS. RUN TBG TO 2130' & SPOT 50 SX CMT INSIDE THE 5 1/2" CASING. PULL TBG TO 930' & PUMP INTO PERFS AT 1230' WITH 50 SX CMT, 25# HULLS THEN 30 SX CMT & DISPLACE AT 500# LEAVING 50 SX CMT OUTSIDE THE CASING & 30 SX CMT INSIDE THE CASING. PERFORATE 2 HOLES AT 336'. CIRCULATE CMT TO SURFACE WITH 110 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Top	Bot	Thru	Comments
4553	4556		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

(TECHNICIAN)

RECEIVED
SEP 29 2016
KCC DODGE CITY

OCT 03 2016 Form CP-2/3
no