

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25390-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 10-16S-26W
970 feet from S Section Line, 3355 feet from E Section Line
Lease Name: PETERS 'D' Well #: 3-10
County: NESS Total Vertical Depth: 4625 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4500		WITH 2 SX CMT
MSCC		2049		WITH 575 SX CMT
PROD	5.5	4623	0	WITH 150 SX CMT
SURF	8.625	352		WITH 215 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2016 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OFS, LLC
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN L LOEB Phone: (618) 943-2227

Proposed Plugging Method: CIBP @ 4500' WITH 2 SX CMT. PLUG AT 2075' TO 0'. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2016 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4500' WITH 2 SX CMT. RUN TBG TO 2070' & FILL CASING WITH CMT FROM 2070' TO 0' WITH 200 SX CMT. PULL TBG & TOP OFF WITH 5 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
4554	4568		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
JA

(TECHNICIAN)

RECEIVED
SEP 29 2016
KCC DODGE CITY

OCT 03 2016

Form CP-2/3