

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21820-00-00
Spot: SWSENWSW Sec/Twnshp/Rge: 8-30S-18W
1475 feet from S Section Line, 4469 feet from E Section Line
Lease Name: PETRA Well #: 1-8
County: KIOWA Total Vertical Depth: 5375 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4940		
CIBP		5030		
PROD	5.5	5163	0	WITH 200 SX CMT
SURF	8.625	634		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/14/2016 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN L LOEB Phone: (619) 432-2227

Proposed Plugging Method: CIBP @ 4940' WITH 2 SX CMT. TEST CASING. PERFORATE AT 1055' WITH 50 SX CMT. PERFORATE AT 680' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2016 12:25 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 4940'. LOADED THE HOLE WITH 59 BBL WATER & PRESSURE TESTED THE CASING TO 500#. PERFORATED AT 1055' & 680'. RAN TBG TO 1054' & PUMPED 25 SX CMT, THEN 25 SX CMT WITH 50# HULLS. PULLED TBG TO 671' & CIRCULATED CMT TO SURFACE WITH 75 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO 5 1/2" X 8 5/8" ANNULUS & PUMPED 40 SX CMT. CMT CIRCULATED.

Top	Bot	Thru	Comments
5038	5042		
5010	5014		
4992	5003		

Remarks: USED 60/40 POZMIX 4% GEL 2% CC BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
SEP 15 2016
KCC DODGE CITY

OCT 03 2016 Form CP-2/3
[Signature] [Signature]