

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-20116-00-00
Spot: NESW Sec/Twnshp/Rge: 1-20S-33W
1963 feet from S Section Line, 3330 feet from E Section Line
Lease Name: PETRO Well #: 1-1
County: SCOTT Total Vertical Depth: 2675 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2673	0	WITH 100 SX CMT
SURF	8.625	314		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/22/2016 2:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: SHANE PELTON Company: HERMAN L LOEB LLC Phone: (719) 340-8985

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/22/2016 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 150# HULLS & 70 SX CMT DOWN 4 1/2" CASING TO 2647'. DISPLACE WITH WATER TO 1650'. RUN CBL FROM 1500' TO 30'. FOUND TOP OF GOOD CMT AT 550'. TOP OF SCATTERED CMT AT 380'. PERFORATE 4 HOLES AT 350'. RUN TBG TO 900'. CIRCULATED CMT TO SURFACE UP THE 4 1/2" CASING AND 4 1/2" X 8 5/8" ANNULUS WITH 145 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2642	2647		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG 25 2016
KCC DODGE CITY

OCT 03 2016 Form CP-2/3

