


15-095-00361-0000

WELL PLUGGING RECORD

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavits
 Mail or Deliver Reports
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

Kingman County. Sec. 5 Twp. 30S Rge. 9W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW
 Lease Owner Sierra Petroleum Co., Inc.
 Lease Name CARTER Well No. 1
 Office Address 208 Petroleum Bldg., Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) dry
 Date well completed 2/19/59 19
 Application for plugging filed 2/18/59 19
 Application for plugging approved 2/18/59 19
 Plugging commenced 2/19/59 19
 Plugging completed 2/19/59 19
 Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampl - Pretty Prairie, Kansas
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4360 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	227	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 4360 up to 210'. Set bridge using 1/3 sack hulls, wood plug and 20 sacks cement through drill pipe. Filled with heavy mud up to 40'. Set bridge using 1/3 sack hulls, wood plug and 10 sacks cement up to cellar 0. 2 sx cement used to plug rat hole down 3'. - Plugger: Fred Hampl - Pretty Prairie Kansas

2-21-59
 RECEIVED
 STATE CORPORATION COMMISSION
 FEB 21 1959
 CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Sierra Petroleum Co., Inc.
 Address 208 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address) _____

SUBSCRIBED AND SWORN TO before me this 20th day of February, 19 59

Margie Cooper

Notary Public.

My commission expires 1-30-61.

PLUGGING
 FILE SEC. 5 T. 30 R. 9W
 BOOK PAGE 16 LINE 22

Sierra Petroleum Co., Inc.

Quarter #1

SE SE SW Sec. 5-30S-9W
Kingman County, Kansas

Total Depth: 4360'

Elev: 1697 KB

Comm: 2/4/59
Comp: 2/19/59

Casings:

8 5/8 @ 227'

Cements:

with 175 sacks cement

FORMATION	DEPTH
Sand	80
Red Bed & shale	160
Red Bed	227
Red Bed & shale	465
Red Bed	750
Shale	1190
Shale & shells	1480
Lime & shale	1540
Lime	1705
Lime & shale	2730
Lime	2855
Lime & shale	3774
Lime	4122
Lime & shale	4298
Chert	4310
Lime & chert	4360

Tops:	Heebner	3438
	Toronto	3454
	Douglas	3468
	Lansing K.C.	3662
	Base of K.C.	4108
	Mississippi	4298

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 21 1959
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) sst
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Hensler

Subscribed and sworn to before me this 20th day of February, 1959.

Margie Cooper
Notary Public

My commission expires: 1-30-61.

PLUGGING
 FILE SEC. 5 T. 30 R. 9W.
 BOOK PAGE 16 LINE 22