


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW%SW%" or footage from lines Barton County, Sec. 20 Twp. 16 Rge. 11 (E) W (W)  
SW NW NW  
Lease Owner Harms Drilling Company  
Lease Name Al Prusa Well No. 1  
Office Address P.O. Box 488 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 29 19 62  
Application for plugging filed August 29 1962  
Application for plugging approved August 29 (Verbally) 1962  
Plugging commenced August 29 1962  
Plugging completed August 29 1962  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3380 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	223'	8 5/8	223'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from total depth to 270' with plug and 25 sacks of cement at this point. Heavy mud to 35' with plug and 10 sacks of cement at this point. 2 sacks of cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 26 1962  
9-26-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms Drilling Company  
Address P.O. Box 488 Great Bend, Kansas


STATE OF KANSAS, COUNTY OF BARTON, ss.  
ALLAN HARMS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms  
P.O. Box 488 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of September, 1962

My commission expires January 22, 1966

Helen E. Gushart  
Notary Public.



D R I L L E R S L O G

COMPANY: Harms Drilling Company  
FARM: Al Prusa #1  
COMMENCED: August 21, 1962

SW NW NW Section 20-16-11W  
Barton County, Kansas  
COMPLETED: August 29, 1962

Elevation: 1895 RB

-----

0 - 130	shale
130 - 155	sand
155 - 223	shale with sand streaks
223 - 390	shale
390 - 490	sand
490 - 750	shale & red bed
750 - 777	anhydrite
777 - 850	shale-red bed
850 - 1500	shale-shells
1500 - 1645	shale-lime
1645 - 2127	lime-shale
2127 - 2740	shale & lime
2740 - 2942	lime
2942 - 2947	shale
2947 - 2980	lime
2980 - 3000	sand
3000 - 3040	sand-shale
3040 - 3335	lime
3335 - 3380	lime & chert
3380	Total depth

**RECEIVED**  
STATE CORPORATION COMMISSION  
SEP 26 1962  
CONSERVATION DIVISION  
Wichita, Kansas

Set 223' of 8 5/8" surface casing. Cemented with 150 sacks of common cement with 2% calcium chloride.

Tops:	Anhydrite	-	750
	Topeka	-	2733
	Heebner	-	2942
	Douglas sand	-	2980
	Brown lime	-	3039
	Lansing- K.C.	-	3058
	Detrital zone	-	3323
	Arbuckle	-	3368

Dry, plugged, and abandoned

A F F I D A V I T

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

I, Allan Harms of the Harms Drilling Company being first duly sworn on oath state:  
I have knowledge of the facts, statements and matters herein contained and the same  
are true and correct.

Allan Harms  
Allan Harms

Subscribed and sworn to before me this 25 day of September, 1962.

Helen E. Gearhart  
Helen E. Gearhart Notary Public

My commission expires: January 22, 1966