

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ford County, Sec. 25 Twp. 25 Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE
Lease Owner Mull Drilling Company, Inc.
Lease Name Indiek Well No. 1
Office Address 1625 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-21 19 66
Application for plugging filed 7-21 19 66
Application for plugging approved 7-21 19 66
Plugging commenced 7-21 19 66
Plugging completed 7-21 19 66
Reason for abandonment of well or producing formation no oil or gas found
in commercial quantities
If a producing well is abandoned, date of last production -- 19 --
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ed Eves, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4915 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	247.61	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 700' and cement with 35 sacks. Mud back to 297' and set plug and cement with 30 sacks. Mud back to 45' and cement with 15 sx. 2 sacks in rat hole. Plugging completed at 2:05 A.M. 7-21-66.

RECEIVED
STATE CORPORATION COMMISSION
AUG 2 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
1425 Wichita Plaza, Wichita, Kansas
(Address)

Subscribed AND SWORN to before me this 27th day of July, 19 66

My commission expires March 3, 1970
Mary J. Brown
Mary J. Brown Notary Public.

RO'ARY DRILLING LOG

OPERATOR: Mull Drilling Company, Inc.
 #1 Indiet
 NE SE SE Section 25-25S-22W
 Ford County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
 Commenced: 7-8-66
 Completed: 7-21-66
 Remarks: Set 247.61' of 8-5/8
 surface pipe with 165 sacks
 GL3 cement.

FORMATIONS:

Soil, Sand, Shale	40'
Shale	137'
Sand	180'
Shale	1065'
Sand	1110'
Shale and Red Bed	1485'
Shale	1505'
Anhydrite	1531'
Shale	2240'
Lime and Shale	3725'
Shale with Lime	3840'
Lime and Shale	4220'
Lime	4325'
Lime and Shale	4392'
Lime	4915'
Rotary Total Depth (D&A)	4915'

RECEIVED
 STATE CORPORATION COMMISSION

AUG 2 1966

CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the
 State of Kansas, County of Sedgwick, this 27th day of July, 1966.

My Commission Expires:
 March 3, 1970

Mary J. Brown

 Mary J. Brown, Notary Public