

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

NORTH

Locate well correctly on above Section Plat

Reno County, Sec. 20 Twp. 24 Rge. 4 (W)
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 2405' south, 945' West of
 Lease Owner Cities Service Oil Co. N/4 Cor.
 Lease Name Scheuchzer Well No. 5
 Office Address Bartlesville, Okla.
 Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
 Date, well completed June 13, 1937 19
 Application for plugging filed Jan. 7, 1941 19
 Application for plugging approved Jan. 7, 1941 19
 Plugging Commenced Jan. 7, 1941 19
 Plugging Completed Jan. 12, 1941 19
 Reason for abandonment of well or producing formation Unprofitable

If a producing well is abandoned, date of last production May 4, 1940 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
 Producing formation Chat Depth to top 3337' Bottom 3391' Total Depth of Well 3391' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
3344-3355'	Show of Oil & Gas			20" 12 1/2" 7"	37' 489' Cem. 3342'	Left in with 275 sacks 2567'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with rock to 3342'; wood plug and 6 sacks cement to 3320'; filled with mud to 489'; wood plug, 5' rock, 15 sacks cement, mud to within 15' of base of cellar; filled with cement to top.

PLUGGING
 FILE 20, 24 R 4 W
 BOOK PAGE 126 LINE 20

JAN 10 1941
 STATE CORP. COM.
 CONSERV. DIV.

1-18-41

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R.C. Hauber
 Address Cities Service Oil Company, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.
 (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. D. Gates*

Chase, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 17 day of January, 1941

E. B. Busby
 Notary Public.

My Commission Expires Sept. 26, 1942

My commission expires

Cities Service Oil Co.
 formerly
 Empire Oil & Refining Company
 Scheuchzer #5
 Sec. 20, Twp. 24S, R. 4W.
 Reno County, Kansas

~~W. J. SHANAHAN~~
 -DRILLING CONTRACTOR-
 -305 Hoke Building
 -Hutchinson, Kansas-

Rig Started 5-1-37
 Rig Completed 5-5-37
 Drilling started 5-5-37
 Drilling Completed 6-13-37

June 26, 1937

LOG

0 - 8	Cellar	
38	Sand	
138	Sand	
210	Sand	
368	Shale & Shells	
449	Shale & Shells	
489	Shale & Shells	
530	Shale & Shells	
658	Shale & Shells	
740	Lime Shells & Shale	
855	Shale & Lime Shells	
978	Shale & Lime Shells	
1000	Red Rock	- - - - -Driftmeter test 0 degrees off
1070	Shale & Lime Shells	
1080	Red Rock	
1090	Lime Shells & Shale	
1225	Broken Lime	
1393	Broken Lime Shells & Shale	
1530	Shale	
1540	Shale	
1545	Lime	
1615	Shale & Lime	
1700	Sand Shells & Shale	
1732	Lime Shells & Shale	
1846	Shale & Lime & Shells	
2012	Shale & Lime & Shells	- - - - -Driftmeter test 0 degrees off
2067	Sandy Lime & Shells	
2167	Shale & Shells	
2235	Broken Lime	
2278	Lime	
2358	Lime	
2424	Shale & Lime	
2500	Broken Lime	
2529	Lime	
2539	Shale	
2600	Shale	
2620	Lime	
2700	Broken Lime	- - - - -Driftmeter test 0 degrees off
2750	Lime	
2798	Lime	
2874	Lime	
2915	Lime	
2931	Lime	
2965	Lime Sand	
3020	Lime	
3066	Lime	
3120	Shale & Lime	
3140	Shale	
3155	Lime	

PLUGGING
 FILE SEC 20, 24, 4W
 BOOK PAGE 126 LINE 32

15-155-03033-0000

~~E. J. STAUFFER~~

~~DRILLING CONTRACTOR~~

~~305 Hoke Building~~

~~Hutchinson, Kansas~~

Log on Scheuchzer #5

June 26, 1937

Empire Oil & Refining Company P. 2

- 3165 Shale
- 3170 Lime Broken
- 3178 Shale
- 3227 Shale
- 3237 Lime Shells
- 3275 Shale & Shells
- 3310 Shale
- 3320 Shale
- 3325 Shale
- 3330 Shale
- 3333 Shale
- 3334 Shale & Chert
- 3338 White Chert
- 3344 Chat
- 3364 Chat
- 3369 Chat
- 3390 Chat
- 3391 Chat

SET 489'2" of 12 1/2" SURFACE CASING. CEMENT WITH 275 sacks PORTLAND CEMENT 5-10-37 HALLIBURTON METHOD.

SET 3337'8" of 7" O.D. CASING. CEMENTED WITH 224 SACKS ATLAS CEMENT @ 5:00 P.M. 5-28-37 HALLIBURTON METHOD.

PLUGGING

FILE SET 20 24 40

BOOK PAGE 126 LINE 30

5/28/37
C. J. ...