

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

5-8-79

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

API Number 15 - 185-20433-0000 MAY - 8 1979 (of this well)

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name W.L. Kirkman, Inc.
Complete Address Box 18611 Wichita, Ks. 67207
Lease Name Koelsch Well No. 1
Location 150' NW SE NE SW Sec 25 Twp. 24S Rge. 14 (E) (W) X
County Stafford Total Depth 2700
Abandoned Oil Well ~~X~~ Gas Well ~~X~~ Input Well ~~X~~ SWD Well ~~X~~ D & A ~~X~~
Other well as hereafter indicated _____
Plugging Contractor Kelso Casing Pulling
Address Box 176 Chase, Ks. 67524 License No. 683
Operation Completed: Hour / Day 3:45 Pm. Month 5 Year 1979

The above well was plugged as follows:

257' 8 5/8" casing w/250 sax cement. 5 1/2" casing set @ 2648' w/225
sax cement. Preforation @ 2474' & 1948' - Sand back to 1900' - Top sand
w/5 sax mixed cement w/ dump bailer. Pull 1710' 5 1/2" casing. Sun
mixed & pumped 5 sax hulls- 20 sax gel- release plug-mixed & pumped
125 sax 50/50 posmix cement w/2% gel & 3% cc to top of casing.
Shut in w/ "0" pressure.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5-9-79

INV. NO. 9609-11