

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 20 1965
12-20-65

Operator's Full Name Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Westerman Unit Well No. # 1

Location NW SW SW Sec. 8 Twp. 30 Rge. 9 (E) (W)W

County Kingman Total Depth 4375'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No. _____

Operation Completed: Hour 2:30 PM Day 19th Month Dec. Year 1965

The Above well was plugged as follows:

207' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fluid
level in the hole was at 100'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 200', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Pauline Elving
Well Plugging Supervisor

DATE 12/20/65
INV. NO. 2446-W