

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1968

CONSERVATION DIVISION
Wichita, Kansas

2-26-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Well Plugging Authority,
issued February 9, 1968.

Operator's Full Name Pan American Petroleum Corporation

Complete Address: P. O. Box 432, Liberal, Kansas 67901

Lease Name Twyman Gas Unit Well No. # 1

Location SW NE Sec. 3 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4290'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12:45 PM Day 23rd Month February Year 1968

The Above well was plugged as follows:

242' of 8 5/8" surface pipe, cemented with 175 sacks. 4274' of 4 1/2" long string
cemented with 150 sacks. Plug back T.D. 4244'. Top perforation 4216'. Cast
iron bridge plug was set at 3850', and cemented with 3 sacks, with cement
from 3850' to 3802', cemented through the dump bailer. 2709' of 4 1/2" long
string was recovered from the hole. Fluid in the hole was bailed down to 240',
bridge plug and rock bridge from 240' to 230', and cemented with 25 sacks,
with cement from 230' to 155'. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base
of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/26/68
INV. NO. 7329-W

Signed: Aubie Elving
Well Plugging Supervisor