

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 5 1964  
3-5-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Sinclair Oil & Gas Company

Complete Address: Box 521, Tulsa 2, Oklahoma

Lease Name Joe Prusa Well No. # 4

Location G SE SE NE Sec. 20 Twp. 16 Rge. 11 (E) W

County Barton Total Depth 3298

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 1 PM Day 3 Month 3 Year 1964

The Above well was plugged as follows:

10 3/4" 103' Gwc.

Sanded hole back to 3260' & dumped 5 sax cement with dump bailer.

Pulled pipe; circulated hole with mud @ 360'. Pulled pipe to 240';

displaced 30 sax cement thru pipe. Pulled remaining pipe; set rock

bridge @ 30' & displaced 10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Truitt  
Well Plugging Supervisor

DATE 3/5/64  
INV. NO. 8749-u