



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION ~~7th~~ ^{NW} NW 5E

SEC. 20 TWP. 16 RGE. 11-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 6 Lease Mary Prusa

Operator Sinclair & Co ^{PRAIRIE} Address Great Bend - Kans.

Field _____ County Barton

Total Depth 3301 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 2 3/4 300ft - Circulated with Cement
7" casing set at 2895ft - Filled back from bottom
to 2820ft Bridge & 15 sacks of cement in the 7" casing
at 2820ft - Shut off & recovered 1550ft of 7" casing
Filled with mud to 300ft - Bridge & 20 sacks Cement -
Mud to 25ft - Plug & 10 sacks of cement -
Shuman & Willey - Pipe Pulling Contractors -

PLUGGING
FILE SEC 20 T 16 R 11W
BOOK PAGE 27 LINE 27

C. M. Stough
District Conservation Agent

Date 5-4-48 MAY 8

5-6-48