

15009-19247-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_ *KCC 9-29-16*  
LOCATION SW-<sup>SE</sup>NE-NE  
SEC. 20 TWP. 16 RGE 11W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Joe Purrow

Operator Senclair Oil & Gas Co. Address Chase Kansas

Field \_\_\_\_\_ County Barton

Total Depth 3305 Feet.

Plugging Contractor Must Supply Co. Inc.

Plugging Contractor's License No. 14

Address Box 306 Chase Kansas  
(Describe briefly the manner in which the well was plugged)

*Surface Pipe 13 in. @ 140 c.w.c.  
7 in. at 3222 by 100.4 cent  
7 in collapsed at 2400 sand to 2370 + 5 in.  
cent. Pull pipe and fill <sup>hole</sup> with heavy mud and  
n.b. top at 280 Pump 500 cent Through  
7 in case 2 plugs finish pulling 7 in and fill hole  
with heavy mud and n.b. at 20 feet and 200 cent  
to base of cellar*

R. M. Brundage  
District Conservation Agent

Date April 11-1956

4-12-56

**PLUGGING**  
FILE SEC 20 T 16 R 11W  
BOOK PAGE 53 LINE 4