

sp
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sunray DX Oil Company

Complete Address: 321 West Douglas. Wichita, Kansas

Lease Name Rohlman Well No. 1

Location SE NW Sec. 9 Twp. 24 Rge. (E) (W) 40

County Hamilton Total Depth 2405'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling Company

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 230PM Day 26 Month 1 Year 64

The Above well was plugged as follows:

8 5/8"-140' Circulated w/cement. 4 1/2"-2404' Cemented.

Plug back bottom w/cement 2405' to 2399' Perforations 2393' to 2390'

Plug bottom w/5 Sax.cement 2399' to 2339' Mud 2339' to 600'

25 Sax.cement 600' to 525' Mud 525' to 140'

25 Sax.cement 140' to 65' Mud 65' to 50'

Rock bridge 50' to 40' 15 Sax.cement 40' to 0

Company Pump. Pulled 1800' 4 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Hugh Scott*
Well Plugging Supervisor

DATE 1/6/64

INV. NO. 8408-w