

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 14-36

LOCATION NW-NW-SW

SEC. 26 TWP. 14 RGE. N-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3-A Lease Tucker-A

Operator Glenn Supply Co Address Box 1104 Tulsa, Okla

Field _____ County Nowata

Total Depth 3382 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 3/8 - 493 ft - Circulated with cement.
5 7/8 casing set at 3332 ft. Cemented with 100 sacks cement.
Plugged back to 3320 ft. with shot - dumped 5 sacks of
cement at 3320 ft. Shot off & pulled the 5 7/8 casing - filled
with mud to 250 ft. - Set Rock Bridges & 10 sacks
of cement at 250 ft. - Mud to 20 ft. - Bridges &
10 sacks of cement at the surface -
West Supply Co. - Plugging & Extractor

RECEIVED 10-4-50
STATE CORPORATION COMMISSION
OCT 4 - 1950

CONSERVATION DIVISION
Wichita, Kansas
District Conservation Agent [Signature]

Date 10-1-50

PLUGGING
FILE SEC. 20 T. 14 R. 40
BOOK PAGE 14 LINE 36