

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mull Drilling Company

Complete Address 415 Page Court, 220 W. Douglas, Wichita, Kansas

Lease Name Regnier Well No. 1

Location C NW SE Sec. 1 Twp. 25 Rge. 22 (E) (W)

County Ford Total Depth 4766'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson

Address 435 Pg. Ct., Wichita, Kansas License No.

Operation Completed: Hour 5:15 AM Day 15 Month 5 Year 1973

The above well was plugged as follows:

8 5/8" to 366' circulated w/ cement. Mud 4766' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 350'

Spotted 35 sacks cement 350' to 250' Mud 250' to 45'

Plug, Hulls ^{ca} 15 sacks cement 45' to 0'. Allied Pump Truck.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar J. Carles*
Well Plugging Supervisor

INVOICED

DATE 5/22/73

INV. NO. 7385-W