

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-057-20,261-0000 ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name T.M. Oil Co. Inc.

Complete Address Union Center Bldg, 150 N. Main Suite 422 Wichita Kansas <sup>67202</sup>

Lease Name Thomas "A" Well No. 1

Location C-SE-NE Sec. 2 Twp. 25 Rge. 22 (East)(West)

County Ford Total Depth 4825'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling Co. Inc.

Address 801 Union Center Wichita Kansas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 12:30 AM Day: 12 Month: April Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

The anhydrite was topped at 1520'. 1st plug at 1500' with 60 sks of cement. 2nd plug push rubber plug to 358' and pumped 40 sks of cement on top of it. 3rd plug on solid bridge at 40' to 0' with 10 sks of cement. Then circulated 10 sks of cement in the rat hole. The cement was pumped through drillpipe with hole full of heavy mud. The plugging was accomplished by Halliburton Co.

Amount of Surface Casing: 369' of 8 1/2" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1982

INVOICED  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: \_\_\_\_\_  
Conservation Division Agent

DATE 4-16-82

INV. NO. 2928-W

15681