

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

*Rec'd
2-17-65*

Operator's Full Name Donald C. Slawson

Complete Address: 407 One Twenty Building. Wichita, Kansas

Lease Name Tassett Well No. # A-1

Location C NW SE Sec. 10 Twp. 25 Rge. 22 (E) (W)

County Ford Total Depth 4932'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co. Inc.

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 4 PM Day 15 Month 2 Year 65

The Above well was plugged as follows:

8 5/8"-303' Circulated w/cement. 4 1/2"-4932' Cemented. Perforations 4791'-4799'

Plug back to 4815' Plug bottom w/sand 4815' to 4775'.

5 Sax. cement 4775' to 4715' Mud 4715' to 310'

Spotted 35 Sax. cement 310' to 210' Mud 210' to 55'

Rock bridge 55' to 45' 15 Sax. cement 45' to 0

Company Pump. Pulled 2725' 4 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/17/65

INV. NO. 694-w

Signed: *Fugh Scott*
Well Plugging Supervisor