

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-079-20557-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Associates Oil & Gas, Inc.

Complete Address 120 E. Market # 501, Wichita, Ks, 67202

Lease Name Schrag Well No. 4

Location SE-SW-NE Sec. 10 Twp. 24 Rge. 3 (~~East~~)(West)

County Harvey Total Depth 465'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Abandoned Location / Lost Circulation

Plugging Contractor White & Ellis Dalg Rig # 10

Address Eldorado, Ks. License No.

Operation Completed: Hour: 3:40 Am Day: 12 Month: April Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

Ran open end drill pipe to 435' - Spotted 50 sks 27 gal 39cc to make sure of solid Bridge. waited 2 1/2 hrs, ran drill pipe to 350' mixed approx 370 sks, circ. Cmb/Top, pulled drill pipe. Ran 1 joint 4 1/2' of 8 7/8" casing w/ landing nipple, Cmt'd solid. hole standing stable. Ran 1 joint 4 1/2' drill pipe in red hole & feed (circ) Cmb approx 20 sks. refilled 8 7/8 approx 8/10 ft 4cmb

20" Drive pipe @ 23' ground level.

Amount of Surface Casing: 8 7/8 @ 47' - KB:

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Merlan W. Thruhl
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

4-16-82

INVOICED

DATE 4-22-82

INV. NO. 1559-E

RECEIVED
STATE CORPORATION COMMISSION

Signed: APR 15 1982
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas