

15-095-20517-0000

Form CP-3

KANSAS

RECEIVED  
STATE CORPORATION COMMISSION  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

OCT 06 1976  
10-6-76  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Gear Petroleum Co

Complete Address 1325 Vickers KSB&T Bldg Wichita, KS

Lease Name Lattimor Well No. 1

Location C SW/SE Sec. 10 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4343

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 11:00 AM Day 4 Month 10 Year 1976

The above well was plugged as follows:

207 ft 8 5/8 surface cemented with 185 sacks. 4343 ft 4 1/2 long string  
cemented with 150 sacks. Top perf. 4284 ft. Sand to 4250 ft. with  
4 sacks cement. Pulled 3230 ft 4 1/2. Pump 3 sacks hulls, 15 sacks  
gel, 100 sacks cement to surface.

Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: [Signature]  
Well Plugging Supervisor

DATE 10-6-76

INV. NO. 3950-W