

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21333-00-00
Spot: CSWSW Sec/Twnshp/Rge: 8-24S-10W
670 feet from S Section Line, 670 feet from W Section Line
Lease/Unit Name: SAUER Well Number: 2
County: RENO Total Vertical Depth: 3840 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: 155 N. MARKET - SUITE 800 PO BOX 48
WICHITA, KS 67201

Conductor Pipe: Size feet: 8/24-80
Surface Casing: Size 8.625 feet: 221 225 SX CMT
Production: Size 5.5 feet: 3834 175 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/11/2002 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/11/2002 4:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Pumped 200lbs of hulls and 50sxs of common. Pressure to 500lbs shut in till morning shot 5 1/2" casing off at 2420'. Pulled to 1450'.
Pumped 35sxs pulled to 900', pumped 35sxs. Pulled to 300' circulate cement to surface.

RECEIVED
KCC DISTRICT #2

JUN 13 2002


WICHITA, KS

Remarks: ALLIED # 7484 60/40 POZ., 4% GEL

Plugged through: CSG

District: 02

Signed


(TECHNICIAN)

INVOICED

DATE

6-24-02

WV. NO.

2002061989