

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21433-00-00  
Spot: SENW Sec/Twnshp/Rge: 8-24S-10W  
3845 feet from S Section Line, 3845 feet from E Section Line  
Lease/Unit Name: SAUER Well Number: 1  
County: RENO Total Vertical Depth: 3880 feet

Operator License No.: 31980  
Op Name: LOTUS OPERATING COMPANY, L.L.C.  
Address: 914 E DOUGLAS  
WICHITA, KS 67202

Conductor Pipe: Size feet: 3/26.10  
Surface Casing: Size 8.625 feet: 219 200 SX CMT  
Production: Size 5.5 feet: 3853 125 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/15/2003 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: TIM HELLMAN Company: LOTUS OPERATION COMPANY, L Phone: (316) 734-8380

Proposed Plugging Method: ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 23 2003

CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI  
Date/Time Plugging Completed: 01/15/2003 12:00 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: JACK LUTHI

Actual Plugging Report:

Set CIBP at 3640', ran 5 sx of common with bailer, shot 5 1/2" casing off at 2410', pulled to 1450', pumped 35 sx, pulled to 1050', pumped 35 sx, pulled to 270', circulated cement to surface.

Remarks: ALLIED #4355 60/40 4%

Plugged through: CSG

District: 02

Signed [Signature]  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-24-03

INV. NO. 2003061108