

5 020177

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15-009-23,995-0000

100' E of SW SE 1/4, SEC. 22, T. 16 S, R. 11 W

330 feet from N(S) section line

3530 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8320

Lease Name Besthorn Well # 1

Operator Name & Address Francis Ensminger
520 E. 10th

County Barton 109.50

Great Bend, Kansas 67530

Well Total Depth 3369 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 525 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co. Inc.

RECEIVED
 STATE CORPORATION COMMISSION
 License Number 5927
 JUL 10 1985
 CONSERVATION DIVISION
 Wichita, Kansas

Address Box 823, Great Bend, Kansas 67530

Company to plug at: Hour: 9:50 AM Day: 6 Month: July

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Co. Inc. (phone) 316 793 8366

were: Fill hole with mud. Pump 50 sacks 60/40 Pozmix w/ 4 1/2 gal
through drill pipe @ 750'. Fill hole with mud. Pump 25 sacks 60/40
Pozmix w/ 6 1/2 gal through drill pipe @ 300'. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Cement rat hole with 10 sacks cement through drill
pipe. Plugging Proposal Received by Delbert J. Tomer
 (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:00 Noon Day: 6 Month: July Year: 1985

ACTUAL PLUGGING REPORT Hole Filled with mud. Pumped 50 sacks 60/40 Pozmix
w/ 4 1/2 gal through drill pipe @ 750'. Filled hole. Pumped 25 sacks
60/40 Pozmix w/ 6 1/2 gal through drill pipe @ 300'. Filled hole with mud
to 40'. Pushed plug and 1/2 sack hulls to 40' and capped hole with
10 sacks Pozmix. Cemented rat hole with 10 sacks Pozmix through
drill pipe.

Remarks: Anhydrite 739-765' NO Ar buckle cut.
 (If additional description is necessary, use BACK of this form.)

INVOICED

(Buyer and Lot) observe this plugging:

DATE 7-17-85

Signed Delbert J. Tomer
 (TECHNICIAN)

INV. NO. 8999