

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-21519-00-00

Spot: NENWNW

Sec/Twnshp/Rge: 29-25S-14E

600 feet from N Section Line, 1000 feet from W Section Line

Lease Name: CORKERY

Well #: 10

County: WOODSON

Total Vertical Depth: 1448 feet

Operator License No.: 32044

Op Name: TRIMBLE & MACLASKEY OIL LLC

Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4	1446		50 SX
SURF	7	83		20 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/21/2016 9:00 AM

Plug Co. License No.: 32044

Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC

Proposal Rcvd. from: RANDALL L. TRIMBLE

Company:

Phone: (620) 836-2000

Proposed
Plugging
Method:

Perf casing at 550' and 250'. 50' bottom cement bridge, gel spacer, 50' cement bridge 550', cement 250' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/21/2016 12:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1356', pumped 20 sxs cement, pulled tubing to 571', pumped 15 sxs cement, pulled tubing to 250', pumped 55 sxs cement to surface, perfed well @ 571' & 250', gel spacers between cement plugs

RECEIVED
KCC DIST # 3
SEP 26 2016
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

District: 03

Signed

Michael Heffern

(TECHNICIAN)

KCC WICHITA

SEP 30 2016

RECEIVED

OCT 04 2016

Heidi Olenick

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **2975**
Foreman Steve Mead
Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-21-16	1000	Conkery #10	29	25	14	Woodson	KS
Customer <u>Trimble & MacLasker</u>			Unit #		Driver		
Mailing Address <u>P.O. Box 271</u>			102		Russ		
City <u>Gridley</u>			110		AB		
State <u>KS</u>			145		Steve		
Zip Code <u>66853</u>							

Job Type PTA Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 2 3/8 Tubing. Break circulation Pump 200' Gel/Spacer.

Spot 20SKS AT 1356'
Spot 15SKS AT 571'
55 SKS 250' to surface
Total 90SKS 60/40 Pozmix Cement 4 1/2% Gel

Job complete Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105.2	1	Pump Charge	500.00	500.00
C107	20	Mileage	3.95	79.00
C203	90SKS	60/40 Pozmix Cement	12.75	1147.50
C206	300*	Gel 4 1/2%	.20	60.00
C206	200*	Gel/Spacer	.20	40.00
C108A	3.57760	Ton mileage Bulk Truck	m/c	345.00
C113	3hrs	8000 Lbs Truck	85.00	255.00
KCC WICHITA				
SEP 30 2016				
RECEIVED				
590 <130.43>				
#2418.06				
SubTotal				2426.50
Sales Tax				181.99
Total				2608.49

Authorization Witness by Brian Title Co. Rep Total 2608.49

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.