

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-25414-00-00

Spot: NENENW

Sec/Twnshp/Rge: 29-25S-14E

4945 feet from S Section Line, 3000 feet from E Section Line

Lease Name: CORKERY

Well #: 17

County: WOODSON

Total Vertical Depth: 1438 feet

Operator License No.: 32044

Op Name: TRIMBLE & MACLASKEY OIL LLC

Address: 110 SOUTH ST. PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1438		50 SX
SURF	7	153		60 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/19/2016 9:00 AM

Plug Co. License No.: 32044

Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC

Proposal Rcvd. from: RANDALL L. TRIMBLE

Company:

Phone: (620) 836-2000

Proposed
Plugging
Method:

Perf casing at 550' and 250'. 50' bottom cement bridge, gel spacer, 50' cement bridge 550', cement 250' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/19/2016 12:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1360', pumped 20 sxs cement, pulled tubing to 570' pumped 15 sxs cement, pulled tubing to 250' pumped 60 sxs cement to surface, perfed well @ 570' & 250', gel spacers between cement plugs.

Top	Bot	Thru	Comments
1412	1420		

RECEIVED
KCC DIST # 3
SEP 26 2016
CHANUTE, KS
MH

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern

(TECHNICIAN)

KCC WICHITA

SEP 30 2016

RECEIVED

OCT 04 2016

Nedra Dennis Form CP-2/3

15-207-25414 0000

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **2955**
Foreman Russell Meloy
Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
9-19-16	1,000	Conkery # 17	29	25	14	Woodson	KS	
Customer Trimble + MacLuskey Oil			Unit #		Driver		Unit #	Driver
Mailing Address P.O. Box 171			102		Russ			
City Gridley			110		AB			
State KS			145		Dnie			
Zip Code 66852								

Job Type P.T.A. Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8
 Casing Depth _____ Hole Size UNKNOWN Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting.
Set Plugs 20 SKs @ 1360
15 SKs @ 570
60 SKs @ 255
95 SKs TOTAL

NOTE Gel spacer between Plugs

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105-2	1	Pump Charge	500.00	500.00
		Mileage	N/C.	
C-203	95	SKs 60/40 Pozmix	12.75	1211.25
C-202	300 #	Gel = 4%	.20	60.00
C-206	200 #	Gel spacer	.20	40.00
C-108		Tow Mileage	m/c	345.00
C-113	2 hr	80 B61 Vac Truck	85.00	170.00
KCC WICHITA SEP 30 2016 RECEIVED				
			SUB TOTAL	21326.25
			Sales Tax	174.41

Authorization by BRINN MACLUSKEY Title CO/Rep Total 2500.12

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.