

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23662-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 3-9S-18W
2200 feet from S Section Line, 2310 feet from W Section Line
Lease Name: GREEN Well #: 1
County: ROOKS Total Vertical Depth: 3550 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3545		170 SX
SURF	8.625	262		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2016 8:30 AM
Plug Co. License No.: 32278 Plug Co. Name: TENGASCO, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: 08/26/2016-Ordered 275 sx 60/40 pozmix 4% gel cement, 300 # hulls and 13 sx gel (1300 #).
08/29/2016- Ordered 200 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations: 3220' - 3264'.
Port Collar at 1364' w/225 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2016 9:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx cement followed by 13 sx gel and 170 sx cement w/200 # hulls. Well went on vacuum.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 20 sx cement. Shut in pressure 300 psi.
Operator is going to let well set til 08/29/2016 then plug.
08/29/2016- Quality Oil Cementing pumped 160 sx cement w/500 # hulls. Casing full of cement.
GPS: 39.29850N -099.31782W

Perfs:

Top	Bot	Thru	Comments
3261	3264		
3220	3222		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1757 PAT BEDORE WITNESSED FIRST HALF OF PLUG.
RICHARD WILLIAMS WITNESSED SECOND HALF.

Plugged through: CSG

District: 04

Received Signed Richard Williams
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

OCT 04 2016

CM

AUG 29 2016

SEP 06 2016
CONSERVATION DIVISION
WICHITA, KS

Nedra Alessio
Form CP-2/3