

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-00814-00-00
Spot: W2SWNE Sec/Twnshp/Rge: 5-23S-17W
3215 feet from S Section Line, 2405 feet from E Section Line
Lease Name: ALDRICH B. Well #: 2
County: PAWNEE Total Vertical Depth: 4275 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 200 W DOUGLAS, SUITE 101
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4160		
PROD	5.5	4274	2085	
SURF	8.625	202		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2016 9:15 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT WITH 150# HULLS. PLUG AT 1160' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 230' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2016 2:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PUMPED 30 SX CMT & 150# HULLS. PUMPED 10 SX GEL & 50 SX CMT AT 1160'. PULL TO 400' & PUMP 50 SX CMT. INTERMITTANT CIRCULATION. PULL TO 230' & PUMP 50 SX CMT. POOR CIRCULATION. TOO. PLUGS 30' TOO DEEP. RUN BACK 7 JOINTS & PUMP 50 SX CMT AT 220'. POOR CIRCULATION. OUT OF CMT. SHUT DOWN & WAIT TO TAG CMT. WAITED 2 1/2 HOURS & TAGGED CMT AT 160'. TOPPED OFF FROM 0-40' WITH 40 SX CMT. HOLE STANDING FULL.

Perfs:

Top	Bot	Thru	Comments
4198	4204		
4124	4126		
4097	4100		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
SEP 29 2016
KCC DODGE CITY

OCT 04 2016 Form CP-2/3
[Signature]