

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22352-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 1-13S-21W
525 feet from S Section Line, 500 feet from W Section Line
Lease Name: ARMBRISTER Well #: 1
County: TREGO Total Vertical Depth: 3928 feet

Operator License No.: 34134
Op Name: TREK RESOURCES, INC.
Address: 4925 GREENVILLE AVE., STE 915
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3890		585 SX
SURF	8.625	211		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TANNER NELSON Company: TREK RESOURCES, INC. DBA Phone: (620) 755-2571

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/200 # hulls and 12 sx gel. Well was never completed. No perforations.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2016 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3844' and pumped 12 sx gel followed by 30 sx cement. Pulled tubing to 1650' and pumped 125 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 20 sx cement. Tied on to backside and squeezed with 30 sx cement. Shut in pressure 200 psi.

GPS: 38.94450 -099.61169

Perfs:

Remarks: QUALITY WELL SERVICE CEMTN TICKET # 6548

Plugged through: TBG

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

AUG 26 2016

SEP 06 2016
CONSERVATION DIVISION
WICHITA, KS

OCT 04 2016

Form CP-2/3
Heena Clements