

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21519-00-00
Spot: NENWNW Sec/Twnshp/Rge: 29-33S-6W
330 feet from N Section Line, 990 feet from W Section Line
Lease Name: ALLEN Well #: 1-29
County: HARPER Total Vertical Depth: 4561 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4561		125 SX
SURF	8.63	260		200 SX
T1	2.375	4516		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/18/2016 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: CARL ENRIGHT Company: _____ Phone: (405) 429-5748

Proposed Plugging Method: Set CIBP @ 4422' and cap with 10 sks cement. Weld on 4.5" pull sub. Cut & pull free pipe. Spot the following cement plugs: 1) @ 1050' spot 35 sks class C Cement. 2) @ 750' spot 35 sks cement. 3) @ 320' spot 90 sks cement and circulate to surface. Cut & cap Well. Dig up rig anchors.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/06/2016 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

TIH w/tubing to set CIBP at 4422'. Released Plug from tubing & circulated casing with drill mud. Spotted 10 sxs cement on CIBP. Recovered 4 1/2 casing from 1626. Ran tubing to 1050', spoteed 35 sxs cement, Pulled tubing to 750', spotted 35 sxs cement, Pulled tubing to 320' & circulated hole to surface with 90 sxs cement.

Remarks: ORR ENT. CLASS C CEMENT.

Plugged through: TBG

District: 02

Signed [Signature] DISTRICT SUPERVISOR
(TECHNICIAN)

OCT 04 2016

Form CP-2/3

[Signature]