

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-21111-00-02
Spot: SESESE Sec/Twnshp/Rge: 11-9S-22W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: VAN LOENEN Well #: 1
County: GRAHAM Total Vertical Depth: 3862 feet

Operator License No.: 5386
Op Name: PRODUCTION DRILLING, INC.
Address: 1023 RESERVATION RD.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3862		150 SX
SURF	8.625	209		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2016 9:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: NICK GABEL Company: PRODUCTION DRILLING, INC. DB Phone: (785) 628-1118

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls. CIBP- 3675'.
Shot perforations at 2250', 1790' and 1100'.
Perforations: 3568' - 3572', 3684' - 3690', 3716' - 3719'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2016 12:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3500' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 3413' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2336' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1240' and pumped 90 sx cement. Good circulation of cement. Pulled tubing out and topped off with 15 sx cement. Tied on to backside and squeezed with 75 sx cement. Shut in pressure 200 psi.

GPS: 39.27837 -099.73610

Perfs:

Top	Bot	Thru	Comments
3716	3719		
3684	3690		
3568	3572		

Received
KANSAS CORPORATION COMMISSION

SEP 19 2016

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY CEMENT TICKET # 1765

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

OCT 04 2016

CM

Heidi Olenick
Form CP-2/3

SEP 17 2016