

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24270-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 18-35S-4E
2979 feet from N Section Line, 2181 feet from E Section Line
Lease Name: FULSOM Well #: 1
County: COWLEY Total Vertical Depth: 3475 feet

Operator License No.: <u>4555</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>ROADRUNNER ENERGY, INC.</u>	PROD	5.5	3480		115 SX
Address: <u>6906 E 108TH ST</u> <u>TULSA, OK 74133</u>	SURF	8.625	226		155 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JAMES GAFFNEY Company: ROADRUNNER ENERGY Phone: (918) 527-9247

Proposed Plugging Method: SET 5.5 CIBP @ 2865'; DUMP 2 SX CEMENT WITH BAILER; PERFORATE 1' 4 SPF @ 330' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/08/2016 8:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2865', DUMP BAILED 2 SX CEMENT ON TOP OF PLUG. TESTED CASING @ 300#, HELD OK. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 280'-281' (4 HOLES). CONSOLIDATED OILWELL SERVICES SWEDGED INTO 5-1/2" CASING, ESTABLISHED CIRCULATION, MIXED & PUMPED 80 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 05:00 PM 09/08/2016. CONSOLIDATED OILWELL SERVICES CEMENT TICKET # 281.

Perfs:

Top	Bot	Thru	Comments
3458	3466		
3389	3395		
2915	2922		

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

OCT 04 2016

Form CP-2/3

Nedra Olenick

1/8