

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-24401-00-00  
Spot: NWSEENW Sec/Twnshp/Rge: 7-35S-8E  
770 feet from N Section Line, 2010 feet from W Section Line  
Lease Name: FULSOM Well #: 2-7  
County: COWLEY Total Vertical Depth: 2709 feet

Operator License No.: <u>4555</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>ROADRUNNER ENERGY, INC.</u>	PROD	5.5	2703		115 SX
Address: <u>6906 E 108TH ST</u> <u>TULSA, OK 74133</u>	SURF	8.625	471		130 SX
	SURF	8.625	477		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2014 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: JAMES GAFFNEY Company: ROADRUNNER ENERGY Phone: (918) 527-9247

Proposed Plugging Method: SET 5.5 CIBP @ 2550'; DUMP 2 SX CEMENT WITH BAILER; PERFORATE 1' 4 SPF SQUEEZE HOLES @ 575' @ BREAK CIRCULATION & CIRCULATE CEMENT TO SURFACE WITH 60/40 POZ WITH 4% GEL.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/08/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2865', DUMP BAILED 2 SX CEMENT ON TOP OF PLUG. TESTED CASING @ 300#, HELD OK. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 520'-521' (4 HOLES). CONSOLIDATED OILWELL SERVICES SWEDGED INTO 5-1/2" CASING, ESTABLISHED CIRCULATION, MIXED & PUMPED 145 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 09/08/2016. CONSOLIDATED OILWELL SERVICES CEMENT TICKET #280.

Perfs:

Top	Bot	Thru	Comments
2600	2614		

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

Duane Krueger  
(TECHNICIAN)

OCT 04 2016 Form CP-2/B  
Nedra Olenick

1/3