

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23000-00-00
Spot: SWSENE Sec/Twnshp/Rge: 9-8S-22W
1110 feet from N Section Line, 450 feet from E Section Line
Lease Name: ROBERTS Well #: 1
County: GRAHAM Total Vertical Depth: 3590 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3588		110 SX
SURF	8.625	230		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2016 11:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TODD A. BROWN Company: RUSSELL OIL, INC. DBA Phone: (785) 445-6270

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/ 400 # hulls and 11 sx gel Port Collar at 1739' w/250 sx cement. Perforations: 3486' - 3490'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2016 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 50 sx cement followed by 11 sx gel, followed by 110 sx cement. Shut in pressure 1000 psi. Tied on to backside and pumped 5 sx cement. Shut in pressure 200 psi.

GPS: 39.37619 -099.77251

Perfs:

Top	Bot	Thru	Comments
3486	3490		

Received
KANSAS CORPORATION COMMISSION

SEP 19 2016


CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY CEMENT TICKET # 1763

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

OCT 04 2016

cm

SEP 12 2016



HEIDI OLENICK
FORM P-2/3