

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23018-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 9-8S-22W
2220 feet from N Section Line, 1100 feet from E Section Line
Lease Name: ROBERTS Well #: 2
County: GRAHAM Total Vertical Depth: 3591 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3587		85 SX
SURF	8.625	270		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2016 9:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TODD A. BROWN Company: RUSSELL OIL, INC. DBA Phone: (785) 445-6270

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 400 # hulls and 11 sx gel.
Port Collar at 1745' w/175 sx cement.
Perforations: 3398' - 3403', 3496' - 3499'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2016 11:00 AM KCC Agent: MARVIN.MILLS

Actual Plugging Report:

Tied on to casing and pumped 50 sx cement w/200 # hulls, followed by 11 sx gel, followed by 170 sx cement. Shut in pressure 500 psi. Tied on to backside and pumped 5 sx cement. Shut in pressure 300 psi.

GPS: 39.37316 -099.77496

Perfs:

Top	Bot	Thru	Comments
3496	4399		
3398	3403		

Received
KANSAS CORPORATION COMMISSION

Remarks: QUALITY CEMENT TICKET # 1762

Plugged through: CSG

SEP 19 2016

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed _____

(TECHNICIAN)

OCT 04 2016

SEP 12 2016

Nedra Olenick
CP-2/3