

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-21306-00-00
Spot: NWSENE Sec/Twnshp/Rge: 9-3S-41W
1800 feet from S Section Line, 2300 feet from W Section Line
Lease Name: WALTERS Well #: 1-9
County: CHEYENNE Total Vertical Depth: 5382 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2101 CEDAR SPRINGS RD, STE 1500
DALLAS, TX 75201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5379		1090 SX
SURF	8.625	305		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/07/2016 9:00 AM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: JAMES KREHMEYER Company: ROSEWOOD RESOURCES Phone: (970) 630-3880

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 500 # gel and 500 # hulls.
8 5/8" surface casing set at 305' w/185 sx cement.
4 1/2" production casing set at 5379' w/1090' sx cement. TOC 610'.
TD 5382'. PBD 4562'.
Perforations: 4517' - 4531'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/07/2016 9:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4481' and pumped 500 # gel followed by 60 sx cement w/250 # hulls. Pulled tubing to 3453' and pumped 115 sx cement w/100 # hulls. Pulled tubing to 1737' and pumped 115 sx cement. Circulated cement to surface. Pulled tubing to surface. Connected to 4 1/2' production casing and pumped 20 sx cement. Connected to 8 5/8' surface casing and pumped 0 sx cement. Immediate pressure to 400 psi.

GPS: 39.80505N -101.92864W

Perfs:

Top	Bot	Thru	Comments
4517	4531		

Received
KANSAS CORPORATION COMMISSION
SEP 19 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED OIL WELL SERVICES LLC TICKET # 51,555

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

SEP 12 2016

OCT 04 2016
Nedra Clements
CP-2/3