

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-10102-00-00
Spot: NWSWNW Sec/Twship/Rge: 30-32S-12W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WADSWORTH Well #: 1
County: BARBER Total Vertical Depth: 4520 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4425		WITH 2 SX CMT
PROD	5.5	4520	2104	WITH 125 SX CMT
SURF	8.625	321		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/08/2016 1:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: RANDY GNIEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: CIBP @ 4425' & 2 SX CMT. PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40-0' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE
Date/Time Plugging Completed: 08/08/2016 5:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

Perfs:

SET CIBP @ 4425' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 35' WITH 20 SX CMT.

Top	Bot	Thru	Comments
4476	4492		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
AUG 19 2016
KCC DODGE CITY

OCT 04 2016

Heidi Olsen 28-213