

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22119-00-00
Spot: W2NENW Sec/Twnshp/Rge: 32-29S-11W
4614 feet from S Section Line, 3640 feet from E Section Line
Lease Name: BLACKWELDER Well #: 3-32
County: PRATT Total Vertical Depth: 4002 feet

Operator License No.: 5047
Op Name: RUPE OIL COMPANY, INC.
Address: 111 WHITTIER # 1000 PO BOX 783010
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3680		WITH 2 SX CMT
PROD	4.5	3999	2154	WITH 280 SX CMT
SURF	8.625	275		WITH 180 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/05/2016 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 3775' & 4 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/05/2016 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3680' & PUT 2 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 723' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3824	3827		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

SR

OCT 04 2016

Nedra Dennis EDCP-2/3

RECEIVED
AUG 25 2016
KCC DODGE CITY