


WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 212 No. Market
 Wichita, Kansas

NORTH



Locate well correctly on above
 Section Plat

Russell County, Sec 15 Twp 15S Rge. 12W (W)
 Location as "NE/CNW%SW%" or footage from lines NW SW NE
 Lease Owner Theodore Gore
 Lease Name Miller Well No. 4
 Office Address 650 Fourth Nat'l Bank Bldg., Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 10-28-67 19
 Application for plugging filed 10-28-67 19
 Application for plugging approved 10-28-67 19
 Plugging commenced 10-28-67 19
 Plugging completed 10-28-67 19
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3183 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 612' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 350', plug, 25 sks. cement through drill pipe
 Mudded to 40', 1/2 sk. hulls, plug, 10 sks. cement
 2 sks. cem. in rathole

NOV 2 1967
 CONSERVATION DIVISION
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
 Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
 Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
 Box 486, Great Bend, Kansas 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 1967

My commission expires April 1, 1971

Ulanda Nichols
 Notary Public

DRILLER'S LOG

COMPANY: Theodore Gore
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: MILLER #4
 LOCATION: NW SW NE SECTION 15-15S-12W
 RUSSELL COUNTY, KANSAS
 COMMENCED: 10-23-67
 COMPLETED: 10-29-67

| | | |
|------|-------------|--------------------------|
| 0 | 248 | Post Rock, Shale |
| 248 | 610 | Shale, Sand, Redbed |
| 610 | 621 | Anhydrite |
| 621 | 1250 | Shale |
| 1250 | 1465 | Shale, Lime |
| 1465 | 1957 | Lime, Shale |
| 1957 | 2330 | Shale, Lime |
| 2330 | 2750 | Lime, Shale |
| 2750 | 2857 | Shale, Lime |
| 2857 | 3035 | Lime |
| 3035 | 3138 | Lime, Shale |
| 3138 | 3183 | Conglomerate & Sand |
| | <u>3183</u> | <u>RTD - D. & A.</u> |

RECEIVED
 OIL & GAS CORPORATION COMMISSION
 NOV 2 1967
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" used surface casing set @ 612' cemented with 300 sacks of Posmix with HA5

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Miller #4 Well, located NW SW NE of Section 15, Township 15 South, Range 12 West, Russell County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 31st day of October, 1967.

Glanda Nichols
 Glanda Nichols

My Commission Expires:
 April 1, 1971