


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15.167.30534.00.00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 17 Twp. 15 Rge. 12 (E) W. (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE NW
Lease Owner Duke & Wood Drilling Company
Lease Name Brack Well No. 1
Office Address Box 123, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 16 1953
Application for plugging filed September 16 1953
Application for plugging approved September 16 1953
Plugging commenced September 16 1953
Plugging completed September 16 1953
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3345 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	268'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 260', set bottom plug with $\frac{1}{2}$ sack hulls and 20 sacks cement. Filled hole to 35', set top plug with $\frac{1}{2}$ sack hulls and 10 sacks cement. Filled hole to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Duke & Wood Drilling Company
Address Box 123, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, SS.
Cecil M. Olson (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Olson

Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of September, 1953

My commission expires April 29, 1957

Wesley L. Looley
Notary Public.
STATE CORPORATION COMMISSION

23-5091-s 8-50-10M

PLUGGING
FILE SEC 17 T 15 R 12W
BOOK PAGE 130 LINE 4

CONSERVATION DIVISION
Wichita, Kansas

9-24-53

15.167.30534.00.00



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

September 25, 1953

Well No. 1
Lease Brack
Description SE NE NW 17-15-12W
County Russell
File No. 130-4

Duke and Wood Drilling Company
Box 194
Great Bend, Kansas

Gentlemen:

The Rules and Regulations of the KANSAS STATE CORPORATION COMMISSION relative to well plugging, require the item or items listed below to be filed with this office.

Please furnish us with the well log

for the above well.

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR
CONSERVATION DIVISION

BY: S. S. Greider
S. S. GREIDER

RECEIVED
STATE CORPORATION COMMISSION
007-1153
CONSERVATION DIVISION
Wichita, Kansas

15.167.30534.00.00

WELL LOG
Brack #1
SE NE NW of Sec. 17-15-12W
Russell County, Kansas

Started: September 4, 1953
Completed: September 16, 1953

Elevation 1862 KB
Anhydrite 775
Heebner 2936 (-1074)
Lansing 3032 (-1170)
Conglomerate 3302 (-1440)
Arbuckle 3342 (-1463)

0-50	Clay and shale
50-60	Sand
60-110	Clay and shale
110-120	Sand
120-165	Shale
165-175	Sand
175-268	Blue shale and red bed
268-775	Clay, shale and red bed
775-808	Anhydrite
808-1230	Shale and shells
1230-1400	Salt and shale
1400-1625	Shale and shells
1625-1810	Shale, shells and coal
1810-2110	Lime and shale
2110-2495	Lime and shale
2495-2725	Lime and shale
2725-2840	Lime
2840-2940	Lime and shale
2940-3075	Lime
3075-3196	Lime
3196-3294	Lime
3294-3302	Lime
3302-3325	Conglomerate
3325-3345	Arbuckle
3345	TOTAL ROTARY DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton SS

I, Lynn O. Duke, of the DUKE & WOOD DRILLING COMPANY
being first duly sworn on oath, state; That I have knowledge of the facts,
statements and matters herein contained and that the same are true and correct.

PLUGGING
FILE SEC 17 T 15 R 12W
BOOK FACE 130 LINE 4

Lynn O. Duke
Partner

Subscribed and sworn to before me this 28th day of September 1953.

Walter C. Cooley
Notary Public
CONSERVATION COMMISSION

My commission expires: April 29, 1953.

007 1 553
CONSERVATION DIVISION
Wichita, Kansas