

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Russell County, Sec. 36 Twp. 15 Rge. 13 (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines NW NW NE

Lease Owner Sunray Oil Corporation

Lease Name L. Sellens Well No. 2

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 19

Application for plugging filed 11-30-48

Application for plugging approved 11-29-48

Plugging commenced 11-25-48

Plugging completed 11-25-48

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3383 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle		3363		8-5/8"	529'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Halliburton plug and 15 sax cement at 530'. Fill w/mud to 200'.
Set Halliburton plug and dump 15 sax cement. Fill w/mud to 30'.
Set Halliburton plug and 10 sax cement to bottom of cellar.

RECEIVED
Conservation Div.

DEC - 4 1948

STATE CORPORATION
COMMISSION
KANSAS

12-4-48

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sunray Oil Corporation

Address Box 195, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

G. D. Strother (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, (statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Engineer

Box 195, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3 day of December, 1948

My commission expires April 19, 1952

[Signature] Notary Public.

PLUGGING
FILE SEC 36 T 15 R 34
BOOK PAGE 761 INT 35

15.167.04213.00.00

Sunray Oil Corporation
Piltower Building
Tulsa, Oklahoma

December 2, 1948

L. Sellens #2

NW/4 NW/4 NE/4
Sec. 36-15S-15W
Russell County, Kans.

Contractor: Stickle Drilling Company, Tulsa, Oklahoma

Started: November 21, 1948

Finished: November 25, 1948

DRILLER'S LOG

Cellar	0	4	
Clay	4	40	
Sand	40	80	
Shale	80	100	
Shale & shells	100	560	
Iron & shale	560	400	
Shale & shells	400	445	
Iron & sand	445	455	
Shale	455	520	
Red Bed	520	795	8-5/8" set at 529' w/ 275
Anhydrite	795	855	sz bulk cement
Shale	855	1050	
Red Bed	1050	1225	
Salt & shale	1225	1440	
Shale & shells	1440	1460	
Shale	1460	1500	
Broken lime	1500	1595	
Lime	1595	1908	
Lime & shale	1908	2115	
Lime	2115	2190	
Lime & shale	2190	2385	
Shale	2385	2485	
Lime & shale	2485	2549	
Lime	2549	2820	
Shale	2820	2862	
Lime	2862	3259	
Lime & conglomerate	3259	3360	
Arbuckle	3360	3383 (TD KB)	

D & A Plugged with 15 sacks at 530, 15 sacks at 200 and 10 sacks at 30'.

State of Kansas ()
County of Barton (ss)

I, Fred E. Stickle, do hereby certify that the above is a true and complete log of the Sunray Oil Corporation's #2 L. Sellens, located in the NW/4 NW/4 NE/4 of Sec. 36-15S-15W, Russell County, Kansas.

Fred E. Stickle
Fred E. Stickle

Sworn to and subscribed before me this 2nd day of December, 1948

My Commission Expires April 19, 1952

W. W. Scott
Notary Public

DEC 4 1948
PLUGGING
FILE SEC 36 T 15 R 32 SECTION
BOOK PAGE 70 LINE 35